



CC 16 & 21

RSID000616



9270 S. STRAIN RIDGE ROAD
ADMINISTRATIVE SUBDIVISION
PT. OF SECTIONS 16 & 21, T7N, R1W
MONROE COUNTY, INDIANA
JOB NO. 400693



DESCRIPTION:

A part of the Southwest quarter of Section 16 and a part of the Northwest quarter of Section 21 all in Township 7 North, Range 1 West, Monroe County, Indiana, described as follows:

Beginning at the Southwest corner of said Section 16, thence running on the West line of said Section 16 North 00 degrees 06 minutes 27 seconds West for 660.20 feet, thence leaving said section line and running South 89 degrees 11 minutes 43 seconds East for 53.05 feet and to the real point of beginning, said point being also on the East right-of-way of State Highway No. 37, thence leaving said highway and running South 89 degrees 11 minutes 43 seconds East for 2152.93 feet and to the centerline of the old railroad grade, thence running with the centerline of said old railroad South 24 degrees 30 minutes 39 seconds West for 1510.14 feet, thence leaving said railroad and running North 87 degrees 05 minutes 56 seconds West for 1187.83 feet and to the East right-of-way of State Highway No. 37, thence running with said right-of-way North 18 degrees 10 minutes 45 seconds West for 758.77 feet, thence North 09 degrees 27 minutes 42 seconds West for 501.08 feet, thence North 09 degrees 09 minutes 11 seconds West for 130.68 feet and to the point of beginning. Containing in all 53.08 acres, more or less.




Raymond Graham

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
January 31, 1994

24-88-3

Dear Dad



Raymond Graham
RPE 8409 Ind

Dec 27

22-14

SCALE 1" = 200 FT.
CONTOUR INTERVAL 10 FT.

A PART OF THE SOUTH HALF OF
THE SOUTHEAST QUARTER OF


BLOOMINGTON ENGINEERING COMPANY

ENGINEERS and SURVEYORS
811 ANITA STREET
BLOOMINGTON, INDIANA 47401
Phone 332-2603

RSID000093



Sec 21



Clear Creek Township


Wisley To Waterford
Clear Creek Sec 21

RAYMOND GRAHAM
3215 N. SMITH PIKE
BLOOMINGTON, INDIANA 47401

R.P.E. 8409 INDIANA
November 18, 1976

CICr_K16

NE CORNER, 5 1/2, SW 1/4,
SECTION 21, TWP 7 N., RIW



Raymond Graham
Raymond Graham
Indiana RPE # 8409
3215 N. Smith Pike
Bloomington, Indiana

DESCRIPTION - Warren Wisely
A part of the South half of the Southwest quarter of Section 21, Township 7 North, Range 1 West, Monroe County, Indiana, described as follows; starting at a point on the North line of said South half that is 1298.70 feet West of the Northeast corner of said South half of the Southwest quarter; said point also being on the East right-of-way of an old railroad grade; thence South 18° 25' 54" West on and along said East line for 173.92 feet and to the true point of beginning; thence continuing on and along the East line of said railroad grade the following directions and dimensions; South 18° 18' 15" West for 266.22 feet; South 17° 11' 41" West for 369.87 feet; South 17° 55' 46" West for 146.49 feet; South 01° 19' 53" East for 33.20 feet and to a right-of-way marker; South 29° 48' 57" East for 74.30 feet and to an Access Road right-of-way marker; thence leaving the East right-of-way of said railroad grade and running North 84° 56' 03" East on and along the North right-of-way of said Access Road for 554.63 feet; thence North 00° 24' 40" West for 794.13 feet; thence West for 344.89 feet and to the true point of beginning. Containing in all 9.01 acres more or less.

REAL ESTATE TRANSFER


JAN 5 1977

John W. Davis
Auditor Monroe County, Ind.


21-CC

21

NE CORNER, $5\frac{1}{2}$, SW $\frac{1}{4}$,
SECT. 21, TWP 7N, R1W



DESCRIPTION - Oral Wisely.
A part of the South half of the Southwest quarter of Section 21, Township 7 North, Range 1 West, Monroe County, Indiana, described as follows; beginning at the intersection of the North line of said South half and the East right-of-way of an old railroad grade, said point being 1298.70 feet West of the Northeast corner of said South half of the Southwest quarter; thence South $18^{\circ} 25' 54''$ West on and along said East right-of-way for 173.92 feet; thence East for 344.89 feet; thence North $00^{\circ} 24' 40''$ West for 165.00 feet and to said North line of the South half of the Southwest quarter; thence West on and along said North line for 288.72 feet and to the point of beginning. Containing in all 1.20 acres more or less.




Raymond Graham
Indiana RPE # 8409
3215 N. Smith Pike
Bloomington, Indiana

John W. Davis
Auditor Monroe County, Ind.

TRI CO Surveying & Mapping

Edmund O. Farkas, Registered Land Surveyor

103 West Temperance
P.O. Box 96
Ellettsville, Indiana 47429
Phone: 812-876-2305



I, Edmund O. Farkas hereby certify that I am a Registered Land Surveyor licensed in compliance with the Laws of the State of Indiana; that this plat and the following description correctly represent a land survey completed under my supervision on June 15, 1981; that all monuments shown thereon actually exist and that their location and type are to the best of my knowledge accurately shown.

Edmund O. Farkas
Edmund O. Farkas
Registered Land Surveyor
Ind. Reg. No. SQ114
SURVEYOR


EXHIBIT "A"

812-254-4263
WASHINGTON, INDIANA
47501

CONSTRUCTION CONSULTANT
CIVIL ENGINEERING ————— LAND SURVEYING

MARSTON R. FOWLER, JR. P.E. & L.S.

A part of the South half of the Southeast Quarter of Section
21. Township 7 North, Range 1 West, Monroe County, Ind.



ClCr M17

S.E. CORNER OF S.E. 1/4 OF
SEC. 21, T-7-N, R-1-W,
MONROE COUNTY, INDIANA



& ASSOCIATES

812-254-4263
WASHINGTON, INDIANA
47501

CONSTRUCTION CONSULTANT
CIVIL ENGINEERING — LAND SURVEYING

MARSTON R. FOWLER, JR. P.E. & L.S.

CERTIFICATE OF SURVEY

I hereby certify that I have completed a survey, at the request of The Bloomfield State Bank, for the purpose of locating the boundaries of and the improvements on a 5 acres tract of land situated in the South half of the Southeast Quarter of Section 21, Township 7 North, Range 1 West, Monroe County, Indiana, as described in Deed Record Book 309, page 426, in the Recorder's Office of Monroe County, Indiana.

Upon completion of the field reconnaissance it is apparent that the metes and bounds description as recorded does not close and that the point of beginning, as described in said recorded deed is in error.


It is my opinion that a more appropriate metes and bounds description is as follows:

A part of the South half of the Southeast Quarter of Section 21, Township Seven (7) North, Range One (1) West, Monroe County, Indiana.

Beginning at a point which is 400.78 feet North of and 533.75 feet West of the Southeast corner of the Southeast Quarter of said Section 21; thence West, for a distance of 886.76 feet, to the center of the Smithville-Harrodsburg Road; thence South $00^{\circ}-20'-00''$ W, along the center of aforementioned Road, for a distance of 235.78 feet; thence East and parallel to the south section line for a distance of 989.09 feet; thence along Government line North $02^{\circ}-41'$ West, for a distance of 152.50 feet; thence North $39^{\circ}-06'$ West, for a distance of 50.40 feet; thence North $73^{\circ}-37'$ West, for a distance of 79.30 feet; thence North $32^{\circ}-37'$ East, for a distance of 26.07 feet, to the point of beginning, containing 5.22 acres, more or less.

The original description as recorded was used to draw the Plat of Survey, which indicates the encroachments in their respective position to the accepted boundaries, as described above.

I, Marston R. Fowler Jr., also certify that I am a Registered Land Surveyor, licensed in compliance with the laws of the State of Indiana; that the plat of survey represents a survey completed by me; and that the monuments and improvements shown on said plat are to the best of my knowledge and belief true and correct.





Marston R. Fowler Jr.

L.S. #11238

May 11, 1985

CLEAR CREEK SECTION 21

PHIL
CHAMBERS



DESCRIPTION:

A part of the Northwest quarter of Section 21, Township 7 North, Range 1 West, Monroe County, Indiana, bounded and described as follows:

Beginning at a point that is South 89 degrees 26 minutes 54 seconds East 690.66 feet from the Southwest corner of said Northwest quarter and on the East right-of-way of State Highway Number 37, thence running with said State Highway right-of-way North 05 degrees 37 minutes 21 seconds East for 737 94 feet, thence North 06 degrees 13 minutes West for 900 38 feet, thence North 41 degrees 36 minutes 50 seconds West for 413 40 feet, thence leaving said highway right-of-way and running South 87 degrees 05 minutes 56 seconds East for 1187.83 feet and to the centerline of an old railroad grade, thence running with the centerline of said grade on a curve to the left having a radius of 2864 93 feet for an arc length of 1550.08 feet, thence South 06 degrees 29 minutes 21 seconds East for 375.12 feet, thence leaving said railroad grade and running with the South line of said Northwest quarter North 89 degrees 26 minutes 54 seconds West for 689.17 feet and to the point of beginning. Containing in all 30 29 acres, more or less.

Raymond Graham

Raymond Graham
R.P.E. 8409 L.S. 9978 Indiana
3215 N. Smith Pike
Bloomington, Indiana
June 25, 1986





LAKEVIEW FIRE STATION

JOB NO. 1348

CICr_M13

NE CORNER OF NE 1/4
SECTION 21 T7N, R1W
MONROE COUNTY, IND.



TRUSTEE'S DEED

THE BOARD OF TRUSTEES OF MONROE COUNTY COMMUNITY SCHOOL CORPORATION, a municipal corporation of Monroe County, in the State of Indiana, for and in consideration of the sum of One Dollar (\$1.00) and other valuable considerations not expressed herein, hereby convey all of their right, title and interest in and to the following described real estate in Monroe County, Indiana, to PERRY-CLEAR CREEK FIRE PROTECTION DISTRICT, a municipal corporation of Monroe County, Indiana, to wit:

A part of the Northeast quarter of Section 21, Township 7 North, Range 1 West, Monroe County, Indiana, more particularly described as follows: Commencing at the Northeast corner of said Northeast quarter; thence South 89 degrees 32 minutes 50 seconds West along the North line of said Northeast quarter 1231.72 feet; thence South 00 degrees 27 minutes 10 seconds East 1318.85 feet to the point of beginning, said point being on the West right-of-way of Strain Ridge Road; said point also being the beginning of a tangent curve concave to the West and having a radius of 22,883.30 feet; thence Southwesterly along said curve and said right-of-way 17.66 feet; thence continuing along said right-of-way the next three courses: (1) South 05 degrees 30 minutes 46 seconds West 24.20 feet; (2) South 02 degrees 39 minutes 01 seconds West 100.13 feet; (3) South 05 degrees 31 minutes 00 seconds West 46.80 feet; thence leaving said right-of-way North 87 degrees 42 minutes 60 seconds West 198.70 feet; thence North 05 degrees 30 minutes 46 seconds East 188.69 feet; thence South 87 degrees 47 minutes 34 seconds East 193.64 feet to the point of beginning, containing 0.85 acres, more or less.

Subject to all easements.

This conveyance is subject to the condition that the grantee shall cause to be erected on said real estate a fire department station house and shall use and occupy said real estate for that purpose only. In the event such facility shall not be erected; or, if erected it shall not be used for a fire department station house, the real estate shall revert back to the grantor.

Perry Clear Creek Fire Department
3953 Kennedy Drive
Bloomington, IN 47401

LAKEVIEW STATION

JOB NO. 1348

A part of the Northeast Quarter of Section 21, Township 7 North, Range 1 West, Monroe County, Indiana, more particularly described as follows:

Commencing at the northeast corner of said northeast quarter; thence SOUTH 89 degrees 32 minutes 50 seconds WEST along the north line of said northeast quarter 1231.72 feet; thence SOUTH 00 degrees 27 minutes 10 seconds EAST 1318.85 feet to the point of beginning, said point being on the west right-of-way of Strain Ridge Road; said point also being the beginning of a tangent curve concave to the west and having a radius of 22,883.30 feet; thence southwesterly along said curve and said right-of-way 17.66 feet; thence continuing along said right-of-way the next three courses: (1) SOUTH 05 degrees 30 minutes 46 seconds WEST 24.20 feet; (2) SOUTH 02 degrees 39 minutes 01 seconds WEST 100.13 feet; (3) SOUTH 05 degrees 31 minutes 00 seconds WEST 46.80 feet; thence leaving said right-of-way NORTH 87 degrees 42 minutes 40 seconds WEST 198.70 feet; thence NORTH 05 degrees 30 minutes 46 seconds EAST 188.69 feet; thence SOUTH 87 degrees 47 minutes 34 seconds EAST 193.64 feet to the point of beginning, containing 0.85 acres, more or less. /

This certification does not take into consideration additional facts that an accurate and correct title search and/or examination might disclose.

Evidence of easements have not been located in the field and are not shown on this survey drawing.

Subject to the above reservation, I hereby certify that the survey work performed on the project shown hereon was performed either by me or under my direct supervision and control and that all information shown is true and correct to the best of my knowledge and belief.

Certified this 11th day of January, 1989.



Ben E. Bledsoe

Ben E. Bledsoe
Registered Land Surveyor No. S0559
State of Indiana



STRAIN RIDGE SURVEY

Job N=1013



SW. Corner of NE 1/4,
Section 21, T.7N., R.1W.,
Monroe Co., Ind.

CICr_K15

STRAIN RIDGE ROAD
TRACT C & D
JOB NO. 1013

A part of the South half of the Northeast quarter and a part of the North half of the Southeast quarter of Section 21, Township 7 North, Range 1 West, Monroe County, Indiana, more particularly described as follows:

COMMENCING at the southwest corner of said northeast quarter; thence NORTH 80.00 feet; thence East 1150.00 feet to the point of beginning; thence NORTH 50.00 feet; thence East 200.00 feet; thence SOUTH 200.00 feet; thence WEST 200.00 feet; thence NORTH 150.00 feet and to the point of beginning, containing 0.92 acres, more or less.

This certification does not take into consideration additional facts that an accurate and correct title search and/or examination might disclose.


Evidence of easements have not been located in the field and are not shown on this survey drawing.

Subject to the above reservation, I hereby certify that the survey work performed on the project shown hereon was performed either by me or under my direct supervision and control and that all information shown is true and correct to the best of my knowledge and belief.

Certified this 12th day of July, 1989.

Ben E. Bledsoe

Ben E. Bledsoe
Registered Land Surveyor No. S0559
State of Indiana





Polle 16

Raymond Graham


RAYMOND GRAHAM


RPE 8409 L S 9978

3215 N Smith Pike

Bloomington Ind

July 31, 1992





Graham


JAN


5997

16 P. 12

1992

1992






Existing Acres
At present

Graham

1414
L 59970
146 P. 15-
1466 Ind
1, 1992



CC 21

1

- 5/8" REBAR SET
- ▲ P.K. NAIL SET
- IRON PIPE FOUND

586°57'51"W 682.79'
586°43'01"W 1069.27'
586°57'51"W 1012.49'
CENTERLINE 25' I.E. & U.E.

The map shows two adjacent parcels, Parcel #1 and Parcel #2, with the following details:

- Parcel #1:** Located on the right, containing a 2-STRY HOUSE. Its boundaries are: North (150.82'), East (150.02'), South (265.08'), and West (264.68').
- Parcel #2:** Located on the left, containing a GARAGE and a SINKHOLE. Its boundaries are: North (139.16'), East (149.39'), South (150.02'), and West (130.00').
- Centerline:** A 15' U.E. (Utility Easement) runs between the parcels.
- Proposed Septic:** A dashed line indicates a proposed septic system location.
- Point A:** Located at the southwest corner of Parcel #2, with coordinates 997.40' N and 321.62' W.
- Point B:** Located at the southeast corner of Parcel #1, with coordinates 1000.52' N and 264.68' W.
- Other Features:** A dashed line indicates a proposed septic system location. A small rectangular feature is labeled 'EXIST. SEPTIC'.

"POINT A"
997.40' N
321.62' W

"POINT B"
1000.52 N
264.68'W

1015.00 NORTH OF SE
CORNER, SE 1/4, SECTION 2
T7N, R1W, MONROE CO, IN

Douglas R. Curry Oct. 25, 1993
DOUGLAS R. CURRY
INDIANA L.S. #890006
Drawing Revised 11-5-93 D.R.C.



CURRY LAND SURVEYING

Douglas R. Curry
Registered Land Surveyor

(812) 332-9037


3328 S. Walnut, Suite 1A

Bloomington, IN 47404

CURRY LAND SURVEYING

Douglas R. Curry
Registered Land Surveyor

PART 5 1/2 - NE 1/4 SECTION 21 - T74N - R14W



DESCRIPTION:


A part of the South half of the Northeast quarter of Section 21, Township 7 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point that is 330.00 feet North and 1137.94 feet East of the Southwest corner of said half quarter, thence running East for 180.00 feet and to the centerline of Strain Ridge Road, thence running with said road centerline South 06 degrees 15 minutes 14 seconds West for 201.20 feet, thence leaving said road and running West for 146.11 feet, thence South for 50.00 feet, thence West for 11.97 feet, thence North for 250.00 feet and to the point of beginning. Containing in all 0.79 acres, more or less. Subject to a 30.00 foot easement from the centerline of said Strain Ridge Road for County Highway right-of-way.

Subject to and with the use of a 50.00 foot ingress and egress easement across the above described property to Strain Ridge Road and being described on page two.




Raymond Graham R.L.S. 9978 Indiana
Graham Engineering 615 W. Kirkwood
Bloomington, Indiana 47404
October 19, 1998 Job No. 98-627

PART S $\frac{1}{2}$ - NE $\frac{1}{4}$ SECTION 21 - T 7N - R 1W



DESCRIPTION:

A part of the South half of the Northeast quarter of Section 21, Township 7 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at a point that is 330.00 feet North and 803.32 feet East of the Southwest corner of said half quarter, thence running East for 334.64 feet, thence South for 250.00 feet, thence West for 334.64 feet, thence North for 250.00 feet and to the point of beginning. Containing in all 1.92 acres, more or less.

Subject to and with the use of a 50.00 foot ingress and egress easement across the above described property to Strain Ridge Road and being described on page two.



Raymond Graham
 Raymond Graham R.L.S. 9978 Indiana
 Graham Engineering 615 W. Kirkwood
 Bloomington, Indiana 47404
 October 19, 1998 Job No. 98-627

DESCRIPTION 50.00 FOOT INGRESS AND EGRESS:


A 50.00 foot ingress and egress easement being in a part of the South half of the Northeast quarter and a part of the North half of the Southeast quarter of Section 21, Township 7 North, Range 1 West in Monroe County, Indiana, the centerline being more particularly described as follows: Beginning at the Southwest corner of the said Northeast quarter, thence running South for 53.09 feet and to the centerline of said easement and to the true point of beginning, thence running with the centerline of said 50.00 foot easement, the following directions and dimensions, North 59 degrees 08 minutes 47 seconds East for 150.78 feet, thence North 74 degrees 55 minutes 45 seconds East for 139.30 feet, thence North 57 degrees 48 minutes 47 seconds East for 134.90 feet, thence North 69 degrees 16 minutes 29 seconds East for 34.90 feet, thence North 89 degrees 08 minutes 22 seconds East for 29.29 feet, thence South 75 degrees 48 minutes 06 seconds East for 60.83 feet, thence South 67 degrees 35 minutes 00 seconds East for 85.25 feet, thence South 77 degrees 06 minutes 09 seconds East for 86.29 feet, thence South 84 degrees 09 minutes 00 seconds East for 63.83 feet, thence North 84 degrees 34 minutes 58 seconds East for 38.66 feet, thence North 82 degrees 47 minutes 57 seconds East for 57.20 feet, thence North 66 degrees 20 minutes 26 seconds East for 35.91 feet, thence North 89 degrees 57 minutes 17 seconds East for 252.63 feet, thence North 80 degrees 25 minutes 15 seconds East for 74.21 feet, thence South 89 degrees 33 minutes 20 seconds East for 54.14 feet, thence South 82 degrees 02 minutes 08 seconds East for 60.44 feet and to the centerline of Strain Ridge Road.



Raymond Graham


Raymond Graham R.L.S. 9978 Indiana
Graham Engineering 615 W. Kirkwood
Bloomington, Indiana 47404
October 19, 1998 Job No. 98-627

CC 21
PART SECTION 21 - T7N-12W



Raymond Graham


Raymond Graham L.S. 9978 Indiana
Graham Engineering 615 W. Kirkwood Ave.
Bloomington, Indiana 47404
October 21, 1998 Job No. 98-627




N

1" = 200'

● = DENOTES 5/8" REBAR SET W CAP
CAP - GRAHAM L.S. 9978



DESCRIPTION:
A part of Section 21, Township 7 North, Range 1 West, Monroe County, Indiana, described as follows: Beginning at the Southwest corner of the Northeast quarter in said Section 21, thence running North for 330.00 feet, thence East for 803.32 feet, thence South for 250.00 feet, thence West for 295.32 feet, thence South 23 degrees 21 minutes 52 seconds West for 272.33 feet, thence West for 400.00 feet, thence North for 5.00 feet, thence West for 1320.00 feet, thence North for 165.00 feet, thence East for 1320.00 feet and to the point of beginning. Containing in all 12.21 acres, more or less. Subject to and with the use of a 50.00 foot ingress and egress and easement across the above described property to Strain Ridge Road as described on page two.



Raymond Graham
Raymond Graham R.L.S. 9978 Indiana
Graham Engineering 615 W. Kirkwood
Bloomington, Indiana 47404
October 19, 1998 Job No. 98-627

r's Certificate is shown on page one. The margins and format of this
line and spacing may be altered to suit so long as the finished form
net size for the reports shall be no less than 8 1/2 inches by 11 inches
r 14 inches. The surveyor name, initials and phone number may be
in if desired.

SUBJECT + -5 ACRES
" 4 MW A MB

 $2a$

NORTH-500 (250)
STRAIN RIDGE
ROAD

LEGAL DESCRIPTION - JOB NO. 500107

Owners: William E. Belcher & Maxine J. Belcher and

Fred H. Belcher & Elizabeth A. Belcher

Source: Deed Record 386, Page 85

48.35 ACRES

A part of the north half of the Southeast quarter and a part of the south half of the Northeast quarter of Section 21, Township 7 North, Range 1 West, Clear Creek Township, Monroe County, Indiana, more particularly described as follows:

Beginning at a 5/8 inch diameter rebar with a cap engraved "Bynum Fanyo 890006" (called "monument" for the remainder of this description) set at the northeast corner of said Southeast quarter; Thence on the east line of said Southeast quarter South 00 degrees 04 minutes 31 seconds East (assumed basis of bearings) 1011.75 feet to a monument set on the U. S. Government Fee Taking Line (Deed Record 143, page 287, Office of the Recorder); Thence leaving said east line and on the Fee Taking Line the following courses and calls:

North 43 degrees 19 minutes 21 seconds West 94.26 feet to a concrete marker found;

North 33 degrees 06 minutes 20 seconds West 148.30 feet to a monument set;

North 08 degrees 10 minutes 48 seconds West 135.00 feet to an iron pipe found;

South 16 degrees 15 minutes 11 seconds West 117.76 feet to an iron pipe found;

South 17 degrees 35 minutes 47 seconds West 111.36 feet to an iron pipe found;

South 54 degrees 25 minutes 27 seconds West 121.48 feet to an iron pipe found;

South 89 degrees 04 minutes 27 seconds West 91.30 feet to an iron pipe found;

South 60 degrees 58 minutes 11 seconds East 211.70 feet to an iron pipe found;

South 40 degrees 43 minutes 07 seconds East 158.50 feet to a monument set;

South 29 degrees 06 minutes 07 seconds East 136.46 feet to a monument set on the north line of David J. Young (Deed Record 465, page 464, Office of the Recorder); Thence leaving said Fee Taking Line and on the north line of Young and the north line of James R. Brillhart (Deed Record 435, page 478, Office of the Recorder) North 89 degrees 33 minutes 55 seconds West 631.41 feet to a 5/8 inch diameter rebar with a cap engraved "Curry 890006" found; Thence continuing North 89 degrees 33 minutes 55 seconds West 682.79 feet to a P.K. nail found on the centerline of Strain Ridge Road; Thence leaving said north line and on said centerline North 02 degrees 34 minutes 11 seconds East 452.85 feet; Thence North 02 degrees 23 minutes 33 seconds East 431.14 feet; Thence North 01 degree 07 minutes 23 seconds East 376.26 feet to an iron pin in a highway box found at the beginning of a curve concave east and having a radius of 2570.00 feet; Thence on said curve Northerly 290.60 feet through a central angle of 06 degrees 28 minutes 43 seconds to an iron pin in a highway box found; Thence North 07 degrees 36 minutes 06 seconds East 88.68 feet to a mag nail set on the south line of the Department of Natural Resources (Deed Record 423, page 436, Office of the Recorder); Thence leaving said centerline and on the south line of Natural Resources and Thomas H. Underwood (Deed Record 55, page 229, Office of the Recorder) South 89 degrees 21 minutes 13 seconds East 1300.99 feet to a monument set on the east line of the Northeast quarter of said Section 21, said monument being South 00 degrees 09 minutes 17 seconds West 2310.41 feet (formerly a record distance of 140 rods (2310 feet)) from an iron axle found marking the northeast corner of said Northeast quarter; Thence leaving the south line of Mitchell and on said east line South 00 degrees 09 minutes 17 seconds West 313.37 feet (formerly a record distance of 330 feet) to the point of beginning containing 48.35 ACRES (9.49 acres in the Northeast quarter and 38.86 acres in the Southeast quarter) be the same more or less but subject to all rights-of-ways and easements of records according to a survey by Douglas R. Curry, Registered Surveyor No. 890006 in February of 2001.

SUBJECT to all rights-of-way and easements of records.


SUBJECT to a right-of-way being 25 feet wide along Strain Ridge Road measured from the centerline thereof.

Evidence of easements has not been located in the field and is not shown on the survey drawing.

This certification does not take into consideration additional facts an accurate and correct title search and/or examination might disclose.

Subject to the above reservations, I hereby certify that the survey work performed on the project shown hereon was performed by me or under my direct supervision and control, and that all information shown is true and correct to the best of my knowledge and belief.

Douglas R. Curry February 22, 2001
Douglas R. Curry (Indiana L.S. No. 890006)
Bynum Fanyo & Associates, Inc.
528 N. Walnut St., Bloomington, Indiana 47404



21-7-100
Clear Creek Belcher

REPORT OF SURVEY

Job No. 500107

In accordance with Title 865 of the IAA (Rule 12), a report of survey is required to explain procedures used in establishing the subject property lines and to provide an opinion regarding uncertainties in final corner positions. These uncertainties can result from any of the following factors:

A. AMBIGUITIES IN RECORD DESCRIPTIONS OR PLAT

An analysis of the record deed and the adjoining deeds indicates that the distance of 330 feet in the subject deed may end up being long or short. The 330 feet is dependent upon the distance between the northeast corner of Section 21 and the northeast corner of the Southeast quarter of Section 21. Also, a factor is the seniority of Deed Record 109, page 1; and Deed Record 55, page 229. Courthouse research indicates that these deeds are senior to the subject deed and that their north to south distance of 140 rods (2310 feet) is controlling. Note that 330 feet plus 2310 feet equals 2640 feet, the theoretical distance between the section corner and quarter corner mentioned above. This survey found this distance to exist in the field as 2623.78 feet. Thus, with this difference in length between theoretical and actual measurements and adjusting to monumentation in the field the 330 feet is calculated as 313.37 feet. Thus, the north line of this project is located within a certainty of 0.4 feet (5 inches).

B. AVAILABILITY AND CONDITION OF REFERENCE MONUMENTS

An axle in the pavement exists at the northeast corner of the section. The southeast corner of the section is in the lake but is tied to the U. S. Fee Taking Line information and monuments in the area. The east line of the Northeast quarter is defined by the axle and monuments found in Fairway Knolls and The Pointe. The distance from the northeast corner of the section to the northeast corner of the Southeast quarter is a split of the distance between the northeast corner of the section and the location of the southeast corner of the section.

The monuments found on the Fee Taking Line exist with a reasonable and acceptable tolerance between each other. This survey shows and uses the field measurements between them.

Markers set by this surveyor in October of 1993 are used to establish the south boundary line of this project.


The centerline of Strain Ridge Road is used as a monument on this project.

C. INCONSISTENCIES IN LINES OF OCCUPATION

A portion of a randomly placed field fence protrudes over the north boundary line.

D. THEORETICAL UNCERTAINTY

Traverse closure and random errors caused by survey instrument precision give this project a theoretical uncertainty of 0.50 feet. This meets the requirements of a Class "C" Survey as defined in the survey standards.

 2-22-01
Douglas R. Curry (L.S. No. 890006)
Bynum Fanyo & Associates, Inc.
528 North Walnut St.
Bloomington, IN 47404
812-332-8030

FAIRWAY KNOLLS

A part of the Northwest Quarter of Section 22, and a part of the Northeast Quarter of Section 21, Township 7 North, Range 1 West, Monroe County, Indiana, and being part of "Parcel B" in Deed Record 294, Pages 414 and 415 and also being Page 3 of 13 and 4 of 13 of a quitclaim deed from William F. Kirtley to Point Development Company as recorded in Deed Record 294, Pages 411 through 424 in the Office of the Recorder of Monroe County, Indiana, being more particularly described as follows:

Commencing at the Southeast corner of the Northwest Quarter of Section 22, thence North 89 degrees 46 minutes 58 seconds West along the south line of said Northwest Quarter 2174.83 feet; thence leaving said south line North 00 degrees 13 minutes 02 seconds East 1041.20 feet to the point of beginning; thence South 3 degrees 38 minutes 20 seconds West 50.08 feet; thence North 89 degrees 46 minutes 58 seconds West 449.77 feet; thence South 00 degrees 10 minutes 07 seconds West 396.74 feet; thence North 44 degrees 17 minutes 06 seconds West 286.39 feet; thence North 18 degrees 36 minutes 39 seconds West 298.51 feet; thence North 00 degrees 11 minutes 58 seconds West 547.22 feet; thence North 74 degrees 41 minutes 57 seconds East 95.41 feet to a non-tangent curve the radius point of which bears South 15 degrees 18 minutes 02 seconds East 3789.72 feet; thence along said curve 158.11 feet; thence South 49 degrees 43 minutes 24 seconds East 575.00 feet; thence South 13 degrees 23 minutes 56 seconds East 290.00 feet to the point of beginning, containing 10.73 acres, more or less.

Subject to any easements and/or right-of-ways of record.

I hereby certify that this plat and description represent a recent survey conforming to the Minimum Standard Detail Requirements for Indiana Land Title Surveys, and that all information shown is correct to the best of my knowledge and belief.

Kevin B. Potter

Kevin B. Potter, Indiana L.S. No. S0487

Sept. 29, 1988

Date

DULY ENTERED
FOR TAXATION

OCT 19 1988

Robney J. Brown

Auditor, Monroe County, Indiana

Sheet 1 of 2



See 21 + See 22
Clean Creek

1/2

PART OF
SECTIONS 21 & 22
T1N, R1W

5/8" Solid Iron Rod Find.
N.E. Corner
N.W. 1/4 Sec. 22 ClCr_O13
T7N, R14W

N 89° 58' 38" W 2631.33' (MAGN.)
Basis of Bearing


-R.R. Spike Found
N.W. Corner
N.W. 1/4 Section 22
T7N, R1W

ClCr M13

ClCr 015

S.E. Corner —
N.W. 1/4 Sec. 22
(No Monument
Fnd.)

0 = 5/8" Rebar Set
this Survey



9-29-86

Kevin B. Potter

Kevin B. Potter
Indiana Land Surveyor
50487

UTILITY EASEMENTS ADDED
10/11/88 KBP

Section

6.07 Acres
Iron Pipe Found
132' South and
051' East of
Calculated Corner

10.73 ACRES
(TOTAL)

Section
22

4.66 Acres

True
P.O.B. -
(See Detail
Below)

Old Form -
Type Fence
(Near
Sec. Line)

Iron Pipe Found
6.97' South &
1.49' East of
Calculated Center

Golf Course

Point
on Fence
118.40'
and 2.80'
East of
Calc. Corner

SCALE: 1"=50'

South Line of
N.W. 1/4

+ S.E. Corner
of N.W. 1/4
Sec. 22
T7N, R1W

SHEET 2 OF 2


FAIRWAY KNOLL SUBDIVISION - AMENDMENT ONE

FINAL PLAT

PARTS OF SEC 21 & 22, T 7 N, R 1 W

Monroe County, Indiana

NOVEMBER 17, 1999



INTERESTED PARTIES

PLAT NO.	NAME AND ADDRESS	DEED RECORD
4	STATE OF INDIANA DEPT. NATURAL RESOURCES 402 W. WASHINGTON ST, RM 264 INDIANAPOLIS, IN 46204	DR 445 PG 441
70	BRENNAN HOLDINGS LCC 2250 E. POINTE ROAD BLOOMINGTON, IN 47401	
LOT 18	DAVID & ALVERA SHAW 9588 S. POINTE LASALLE DR.	PLAT BK 8, PG 221
LOT 16	THOMAS & JOANN WALKER 9992 ST. ANDREWS LANE BLOOMINGTON, IN 47401	PLAT BK 8, PG 221
LOT 15	QUALITY VILLAGE BUILDERS, INC. 3390 W. 86TH ST, STE 5-5 INDIANAPOLIS, IN 46268	PLAT BK 8, PG 221

COVENANTS AND RESTRICTIONS

AS RECORDED IN PLAT BOOK 8, PAGES 220-221
OFFICE OF THE RECORDER OF MONROE COUNTY, IN
SETBACK REQUIREMENTS

FRONT BUILDING SET BACK LINE IS 15 FEET FROM
I.E. & U. EASEMENT LINE, BEING ROUNDED WITH
5 FOOT RADII AT ALL STREET INTERSECTIONS

REAR YARD BUILDING SET BACK LINE SHALL BE
AS SHOWN ON THE PLAT.

ALL SIDE YARD BUILDING SET BACKS ARE 10 FEET
MINIMUM WITH AGGREGATE DISTANCE BETWEEN
BUILDINGS BEING 30 FEET MINIMUM.

OWNER/DEVELOPER

RENEE E. FARMER
9102 FRONT NINE DRIVE
BLOOMINGTON, IN 47401
(812) 824-2466

SOURCE OF TITLE

INSTRUMENT NO. 1999013522 WARRANTY

PROPERTY NOT IN FLOOD PLAIN

FEMA FIRM PANEL NO. 180444 0006A
EFFECTIVE MARCH 6, 1981

ZONING CLASSIFICATION

PUD - PLANNED UNIT DEVELOPMENT
USE - SINGLE FAMILY RESIDENCE

ENGINEER'S CERTIFICATE

I certify that I am a registered professional engineer licensed under the laws of Indiana; that this plat accurately represents a survey made by me on August 11, 1999; that the monuments shown on it exist; and that their locations, sizes, types and materials are accurately shown.

Raymond Graham
RAYMOND GRAHAM, RPE 8409 RLS 9978
615 W. Kirkwood Avenue
Bloomington, IN 47404 - (812) 336-3509
NOVEMBER 17, 1999 P/N 99-482

